

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 01/19/09.

CORNER DESIGNATION: N-5, The Northwest corner of Section 20, Township 5 North, Range 33 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell and Lewis under Contract No. 110 dated February 7, 1865. Notes state: Set post corner for sections 17, 18, 19, and 20 in land rolling gently to the South. Drove charred stake, dug pits, and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Held the centerline of Muller Road running North-South with a old field berm extending East as the best remaining evidence of the original corner location, after verifying position by measurements to existing corner 1 mile North and probable corner locations, evidenced by road and field intersections, to the South.

MONUMENT MARKING DETAIL:

T5N R33E
S18|S17
S19|S20
2009
PLS 1106

MONUMENT SET: Set a 2 3/8" diameter brass cap on a 1 1/4"x30" galvanized iron pipe, with cap buried 10" below gravel road surface. Cap is marked as shown in "Monument Marking Detail".

New accessories:

A silver Deep-1 magnet buried 20" below ground in farmed field bears North 55° East, 34.4 feet.
A purple Deep-1 magnet buried 20" below ground in farmed field bears South 37 1/2° East, 32.3 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372", 2" above ground level in road bank bears South 20° West, 36.6 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372", 2" above ground level in road bank bears North 14 1/2° West, 33.1 feet.

Buried bearing object signs with all Deep-1 magnets. Attached bearing object signs to iron rebars accessories.

LOCATION AND COMMENTS: Corner is located 10" below Muller Road with field berm extending East.


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

5N33N5



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-10