

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/01/04

CORNER DESIGNATION: V-13, The Northwest Corner of Section 34, T5N., R33E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William H. Odell and William L. Lewis, U.S. Deputy Surveyors under Contract No. 110, dated February 7, 1865. Record states: Set post Cor. to Secs. 27, 28, 33, 34. Drove charred stake; dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was reestablished in a East-West field line/berm, holding the East-West field line for latitude. Departure for corner position was determined by holding record proportional departure from reestablished corner positions 1/2 mile East and West of this corner point.

MONUMENT MARKING DETAIL:

T5N R33E
S28 | S27
S33 | S34
2004
PLS 1106

MONUMENT SET: At a calculated position determined as described, set a 2 1/2" brass cap (marked as shown in "Monument Marking Detail"), on a 1 1/4" x 30" galvanized iron pipe, 30" in the ground and surrounded with earth.

New accessories to corner monument:

The center of a Chevron gas pipeline guard post, at ground level, bears N 66° E, 2.1 feet.
The center of a Chevron gas pipeline guard post, at ground level, bears N 76° W, 3.4 feet.
A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in a rail-road tie fence post bears N 88° E, 36.9 feet.
A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in a rail-road tie fence post bears N 88° E, 93.3 feet.
Nailed bearing object signs to railroad tie fence posts with brass washer accessories. Set steel fence post with witness sign attached 1 foot South of the corner monument.

LOCATION AND COMMENTS: Corner is located in a East-West field line at crossing with the Chevron gas pipe line.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

15N33V13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RECEIVED BY
Umatilla County Surveyor
Date 4-04
Rec'd by KK
No. 04-76-B

renews 6-30-04