

OREGON CORNER RESTORATION FORM

Section 21 Township 5N Range 34E
County UMATILLA Date 10-25-90

CORNER NO. R-9
MAP REFERENCE:
PARTITION PLAT 1990-10

CORNER DESIGNATION

T 5 N R 34 E
S20 | S21
S29 | S28

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. GLO RECORD BY OPELL & LEWIS, CONTRACT NO. 110, DATED FEB. 7, 1865. "POST, CHARGED STAKE & PITS".
RE-ESTABLISHED BY LS 346, IN 1961, MAP Q-783-C.

Monument(s) & Accessories Found: (Condition and Source)


FOUND 12X12X10" STONE BURIED 1' AT CALCULATED CORNER POINT (COULD FIND NO MARKS). THIS STONE IS SUSPECTED TO BE THE ONE SET IN SURVEY Q-783-C, BUT I CAN NOT BE CERTAIN.

Monument Detail

SET 2 1/2" X 30" ALUM. PIPE WITH 2 1/2" ALUM CAP 28" IN THE GROUND & SURROUNDED WITH A MOUND OF EARTH AND STONE. SET STEEL FENCE POST 3' WEST WITH WITNESS CORNER SIGN ATTACHED.

Sketch

CAP MARKED:



Monument Set (Procedures and Description)

RE-ESTABLISHED CORNER POSITION BASED ON SURVEY Q-783-C, BY EXTENDING THE SAME BEARINGS AND DISTANCE OBSERVED BETWEEN THE RECOVERED SOUTHEAST AND SOUTH 1/4 CORNER OF SECTION 21. SEE UMATILLA COUNTY PARTITION PLAT No. 1990-10.

New Accessories

A DOUBLE HEADED NAIL IN THE SOUTHEAST SIDE OF PP&L POLE 210000, 18" ABOVE GROUND, BEARS N17°E 237.4'
A DOUBLE HEADED NAIL IN THE SOUTH SIDE OF PP&L POLE 280900, 18" ABOVE GROUND, BEARS S70 1/2°E - 76.6'
A DOUBLE HEADED NAIL IN THE SOUTH SIDE OF PP&L POLE 299900, 36" ABOVE GROUND, BEARS S56 1/2°E - 41.9'
THE BASE OF A GUYWIRE FOR PP&L POLE 299900

Location & Comments

CORNER LOCATED AT Compass Declination 19°
NE CORNER OF FIELD, Firm/Agency William R.
WEST OF N-S ROAD WELLS, PLS
AT A 3 WAY ROAD Address P.O. Box 1696
INTERSECTION PENDLETON, OR 97801

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RECEIVED BY

Umatilla County Surveyor

Date

Rec'd by KA

No. 91-18-B

Party Chief BILL WELLS

Notes

Witness BILL QUAGMPT