

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 10/07/21.

CORNER DESIGNATION: V-9, the Northeast corner of Section 33, Township 5 North, Range 34 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Odell and Lewis, Deputy Surveyors, under Contract No. 110, dated February 7, 1865. Notes state:

Set a post corner for Sections 28, 29, 32 & 33, drove charred stake, dug pits as per instructions.

The May, 1929 County Road Map for Gerking Flat Road, Constructed Line, shows a tie from the centerline of the road to the corner. The corner monument is unidentified. The County Road Map shows the corner 486 feet West of Road centerline. I measure 487.08 feet from existing road centerline.

MONUMENT AND ACCESSORIES FOUND: None. I reestablish the corner point at the intersection of a fence extending North from North top of bank of road and the visual centerline of Thompkins Road.

MONUMENT MARKING DETAIL:

T5N R34E  
S29 | S28  
-----  
S32 | S33  
2021  
PLS 1106

MONUMENT SET: Set a 2 inch aluminum cap on 5/8 by 16 inch rebar with cap buried 6 inches below gravel road surface of Thompkins Road. Cap marked as shown in Monument Marking Detail.

New accessories:


- A 5/8 by 24 inch rebar with 1 1/4 red plastic cap bears N 57°08' E, 26.6 feet.
- A 5/8 by 24 inch rebar with 1 1/4 red plastic cap bears S 81°43' E, 113.9 feet.
- A 5/8 by 24 inch rebar with 1 1/4 red plastic cap bears S 56°25' W, 32.2 feet.
- A 5/8 by 24 inch rebar with 1 1/4 red plastic cap bears N 57°24' W, 26.6 feet.

Red plastic caps are marked "OR PLS 1106 WA PLS 17372" and have bearing object signs wired to them. Bearings and distances to accessories are State Plane Grid bearings and distances. The rebar accessories are set in the cut bank above the Thompkins Road bed.


LOCATION AND COMMENTS: Corner is located 487 feet West of the visual centerline of Gerking Flat Road, in the centerline of Thompkins Road, in a 20 foot cut in the road.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal



*William R. Wells*



*renews 6-30-22*

\5N34V-9

*PPlat 2021-35  
21-138-B*