

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/24/05

CORNER DESIGNATION: 5N35, J-11, The South Quarter Corner of Section 9.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1 S9
4 S16
2005
PLS 1106

MONUMENT SET:

The corner area falls in a Conservation Reserve Program field that has been extensively farmed. There are no features near the corner area. Corner was re-established by single proportion measurement between the Southwest and Southeast corners of section 9, using record from Odell and Lewis Survey. At the re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 24" below ground level.

New accessories:

- A silver deep-1 magnet buried 20" in ground bears North 71° East, 33.7 feet.
- A purple deep-1 magnet buried 20" in ground bears South 39° East, 27.4 feet.
- A blue deep-1 magnet buried 20" in ground bears South 58° West, 36.9 feet.
- An orange deep-1 magnet buried 20" in ground bears North 32° West, 43.8 feet.

Buried bearing object signs with all deep-1 magnets.

LOCATION AND COMMENTS: Corner located in Conservation Reserve Program field. There are no nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 827534.12
E = 8725532.74

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witness: Jason Wells, LSIT

/5N35J11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-e