

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-13

**History of original corner establishment:**

This corner was originally established by deputy surveyor William S. Lewis on April 11, 1865 under contract no. 110, as follows:


Set a post for the corner and drove a charred stake. Dug pits and raised a mound as per instructions.

County records show this corner was tied to the Tucannon branch line railroad right of way in 1883. The right of way map shows the corner to be 85.5 feet south of the centerline.

Frank Ofner, RPE 2475, conducted a survey of several sections in this township in 1950. Ofner found a "rock" at this corner. His plat does not show bearings and distances between corners, but does show the line between sections 9 and 10 to run west of true north.

**Description of corner evidence found:**

Found unmarked stone as recovered by Ofner. Stone measures 10" x 15" x 24" and is loosely set in a mound of small stones. Centerline of the railroad tracks bears N5°W, 85.5 feet. Fence lines project south and N5°W from the corner. This is the only sizable stone in the vicinity.




**Description of monument and accessories | established to perpetuate the original location of this corner**

Moving the stone aside, I set in it's place a 1 1/2" by 30" galvanized iron pipe with a 2 1/2" brass cap attached, 26" into the ground. The cap is marked as shown in the diagram, above. I placed the large stone along the north side of the pipe and built a mound of stones around the pipe to the cap.

I hereby certify the above corner position was perpetuated as hereon described on May 20, 1988. De: 20°E.

Witness: Floyd Reimers

  
*Dennis L. Gaylord*

Office of COUNTY SURVEYOR County of UMATILLA  
 State of OREGON, I hereby certify that the within instrument was filed in this office  
 for record on the 13 day of JUNE, 1988  
David H. Klein by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor  
 Date 6-88  
KA  
88-23-19