

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/22/05

CORNER DESIGNATION: 5N35, J-17, The Northeast Corner of Section 15.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 10,11, 14 & 15. Drove charred stake; dug pits; raised mound, as per instructions. Original corner was recovered on Record of Private Surveys, Survey No. 5 and Survey No. 36. A 19 x 9 x 8 inch stone was set at the corner point in Survey No. 36. Survey No. Q-805-A calls for a "rock" found at the corner point. Bartleson, in Survey No. 98-82-B set a "5/8" rebar 18" deep", with reference to the recovered Northeast corner of Section 14 and other corner evidence to the North.

**MONUMENT AND ACCESSORIES FOUND:**

A 5/8" rebar with a 1 1/4" yellow plastic cap buried 18" below ground level in a farmed field, per Survey No. 98-82-B. No corner accessories were established.

MONUMENT MARKING DETAIL: Yellow plastic cap on rebar is marked "OR 2166LS".

**MONUMENT SET:**

Maintained corner monument by adding new accessories from the existing corner monument:  
A silver deep-1 magnet buried 20" below ground level, bears North 27° East, 49.7 feet.  
A purple deep-1 magnet buried 20" below ground level, bears South 81° East, 43.2 feet.  
A blue deep-1 magnet buried 20" below ground level, bears South 54° West, 32.8 feet.  
An orange deep-1 magnet buried 20" below ground level, bears North 45° West, 50.8 feet.  
Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Corner is located in a farmed field. There are no nearby features other than a old field berm extending North and East, about 15 feet North of the recovered corner monument.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet;

N = 827797.06  
E = 8733850.83


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Brian Cole

/5N35J17



05-112-c