

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/22/05

CORNER DESIGNATION: 5N35, L-17, The East Quarter Corner of Section 15.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits; raised mound, as per instructions.

Corner was not recovered and was re-established on Record of Private Surveys, Survey No. 5. Notes state: "buried basalt rock 18 x 20 and raised mound, dug pits, etc."

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S15 | S14
2005
PLS 1106

MONUMENT SET:

Corner falls in wheat field about 25' West of the East edge of field. The corner was re-established by single proportion measurement midway between the Northeast and Southeast corners of Section 15. At re-established corner point, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 20" below ground level, marked as shown in Monument Marking Detail.

New Accessories:

A silver deep-1 magnet buried 20" below ground level, bears North 35° East, 37.6 feet.
A purple deep-1 magnet buried 20" below ground level, bears South 38 1/2° East, 32.7 feet.
A blue deep-1 magnet buried 20" below ground level, bears South 62 1/2° West, 25.8 feet.
An orange deep-1 magnet buried 20" below ground level, bears North 31° West, 39.4 feet.
The center of PP&L pole #140561 bears: South 58° East, 113.2 feet.
Buried bearing object signs with deep-1 magnets. Nailed bearing object sign to PP&L pole.

LOCATION AND COMMENTS: Located 25 feet West of the East edge of a farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 825052.08
E = 8733493.70

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35L17



05-112-c