

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/28/05

CORNER DESIGNATION: 5N35, N-23, The South Quarter Corner of Section 13.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits; raised mound, as per instructions.

The corner was not recovered on Record of Private Surveys, Survey No. 5. The corner may have been recovered on Survey No. 16—the notes are not clear, they state “40.25 1/4 sec. post”.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1 S13
4 S24
2005
PLS 1106

MONUMENT SET:

Corner area falls in wheat field with no nearby features. Corner position was re-established by single proportion measurement, midway between the Northwest and Northeast corners of Section 24. At re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 18" below ground level.

New accessories:

- A silver deep-1 magnet buried 20" below ground level, bears North 50° East, 34.3 feet.
- A purple deep-1 magnet buried 20" below ground level, bears South 28 1/2° East, 42.4 feet.
- A blue deep-1 magnet buried 20" below ground level, bears South 44° West, 46.5 feet.
- An orange deep-1 magnet buried 20" below ground level, bears North 46° West, 35.2 feet.
- Buried bearing object signs with deep-1 magnets.
- New City of Milton-Freewater water tank bear North 66° West.

LOCATION AND COMMENTS: Corner is located in a farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 822347.66
E = 8741107.68

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witness: Jason Wells, LSIT

/5N35N23



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RENEWS 6/30/06