

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/10/05

CORNER DESIGNATION: 5N35, P-13, The East Quarter Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

The "government corner" was recovered on Record of Private Surveys, Survey No. 4 and Survey No. 124.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S21 | S22
2005
PLS 1106

MONUMENT SET:

The corner falls in a wheat field with no nearby features. I recovered certain features from J.W. Kimbrell's 1900 Survey No. 124, and held these features to re-establish this corner position, as described in "Detail" on Sheet 2 of 2 of the accompanying Record of Survey. At the re-established corner position, set a 2 1/2" brass cap on a 2 1/2" by 30" galvanized iron pipe with cap 20" below ground surface, marked as shown in Monument Marking Detail.

New accessories:

- A silver deep-1 magnet buried 20" in the ground bears North 61° East, 43.2 feet.
 - A purple deep-1 magnet buried 20" in the ground bears South 53° East, 56.8 feet.
 - A blue deep-1 magnet buried 20" in the ground bears South 63° West, 36.1 feet.
 - An orange deep-1 magnet buried 20" in the ground bears North 46° West, 48.8 feet.
- Buried bearing object signs with all deep-1 magnets.

LOCATION AND COMMENTS: Corner is in a farmed field with no nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 819727.68
E = 8728524.59

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35P13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-C