

**OREGON CORNER RESTORATION FORM**

Section 19 Township 5N  
County Umatilla Date: 01/15/10

Range 35E

Corner Designation: 5N35P5

Corner common to section 19,20 T5NR35E

Condition Report Only  
 Not Found  
 Remonumented  
 Unrecorded  
 Surveyed In  
 Referenced Out


**Previous Renewals / Surveys, etc.**

Surveyed by Wm. H. Odell & Wm. S. Lewis under Contract No. 110, dated February 7th 1865.


**Monuments and Accessories Found: (Condition and Source)**

None.

**Diagram**



**Sketch**



NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N819679.58  
E8717444.82  
LAT - 45° 53' 49.97740" N  
LON - 118° 28' 32.593701" W

**Monument (s) Set (Procedures and Description)**

Set a 1 1/2" Galvanized Iron pipe w/ a 2 1/2" Brass Cap Stamped as shown.  
A 5/8" x 30" Iron Rebar w/ypc #43406 lies N 34° E, 6.28'.  
A 5/8" x 30" Iron Rebar w/ypc #43406 lies S 75° E, 5.95'.  
A 5/8" x 30" Iron Rebar w/ypc #43406 lies S 40° W, 6.92'.  
A 5/8" x 30" Iron Rebar w/ypc #43406 lies N 74° W, 5.51'.

**References Set:**

None

**Location and Comments**

This corner falls near the top of a steep Westerly slope above Pine Creek. Approx. 1-1/2 miles NW of Bill Ferguson Ranch.

**Compass Declination**  
17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
434.06LS

**RECEIVED BY:**

Date: 12-09  
Rec'd By: 09-176-b

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801

RENEWAL DATE: 12/31/11