

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/01/05

CORNER DESIGNATION: 5N35, P-09, The East Quarter Corner of Section 20.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

The corner was not recovered on Record of Private Surveys, Survey No. 27.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1/4  
S20|S21  
2005  
PLS 1106

**MONUMENT SET:**

The corner falls in the middle of a wheat field, there are no nearby features. I re-established corner by single proportion measurement midway between the Southwest and Northwest corner of section 21. At the re-established corner position, set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe with cap 18" below ground level in farmed field. Cap marked as shown in Monument Marking Detail.

**New accessories:**

- A Silver Deep-1 magnet buried 20" in the ground bears North 10° East, 35.7 feet.
- A Purple Deep-1 magnet buried 20" in the ground bears South 73° East, 27.2 feet.
- A Blue Deep-1 magnet buried 20" in the ground bears South 15° West, 32.7 feet.
- A Orange Deep-1 magnet buried 20" in the ground bears North 66° West, 36.8 feet.

Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Corner is located in a farmed field approx. 125 feet East of a field terrace running Northerly.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 819769.34  
E = 8722873.86

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witness: Jason Wells, LSIT

/5N35P09

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*RENEWS 6/30/06*

*05-112-C*