

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/13/05

CORNER DESIGNATION: 5N35, R-17, The Northeast corner of Section 27.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 22,23, 26 & 27. Drove charred stake; dug pits; raised mound, as per instructions.

Survey No. B-1-A, by Harris in 1965, calls for a 1 1/2" pipe. Survey No. 01-97-B, by Harris, in 2001, calls for a 2" I. Pipe.

MONUMENT AND ACCESSORIES FOUND:

Found a 1 1/2" outside diameter iron pipe, set in concrete, protruding 13" above ground level, 1 foot West of railroad tie post in H-brace.

MONUMENT MARKING DETAIL: The corner monument is a 1 1/2" diameter o.d. pipe.

New accessories:

A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in a railroad tie fence post bears South 49° East, 8.7 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap set 1" above ground level, bears South 06° East, 48.0 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap set 1" above ground level, bears North 87° West, 24.6 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap set 1" above ground level, bears North 87° West, 61.1 feet.

Attached bearing object signs to rebar accessories and to railroad tie post with brass washer.

Attached "witness" sign to railroad tie post 1 foot East of monument.

LOCATION AND COMMENTS:

Corner is set in a East -West fence line 8' West of a fence corner and field berm running South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 817140.28

E = 8733760.29

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole
/5N35R17



Will-R. Wells



Renews 6/30/06