

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/28/05

CORNER DESIGNATION: 5N35, R-19, The South Quarter Corner of Section 23.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits; raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1 S23
4 S26
2005
PLS 1106

MONUMENT SET:

Corner was re-established by single proportion measurement between the Northwest and Northeast corners of Section 26. Set a 5/8" x 24" rebar with a 2" aluminum cap, 20" in ground, marked as shown in Monument Marking Detail. Surrounded with a mound of stones.
A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 09° East, 37.5 feet, set on West side of road fill.
A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 36° East, 33.1 feet, set on West side of road fill.
A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 29° West, 26.8 feet.
A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 49° West, 52.9 feet.
Attached bearing object signs to all rebar. Placed "witness sign" in rock mound surrounding corner monument.

LOCATION AND COMMENTS: Corner is set in shallow shell rock hillside about 15 feet West of a road running North to old gravel pit.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 817192.54
E = 8736401.39

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/5N35R19

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06