

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/13/05

CORNER DESIGNATION: 5N35, R-05, The Northwest Corner of Section 29.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 19, 20, 29 & 30, on steep hillside, facing W., drove charred stake, dug pits and made mound, as per instructions.

In Record of Private Surveys, Survey no. 125, J.W. Kimbrell recovers this corner but does not state what was found.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
S19 | S20
S30 | S29
2005
PLS 1106

MONUMENT SET:

I accepted an old fence corner with fences East-West and Northwest as best remaining evidence of the original corner location. There is also evidence of a crooked fence approaching from the Southeast, evidenced by old wire tied to rocks. Mr. Bill Ferguson, neighboring landowner states the fence corner has been in this place for at least 70 years. At the accepted corner point, I set a 5/8" by 24" rebar, driven 20" in the ground to bedrock, and capped it with a 2" aluminum cap stamped as shown in Monument Marking Detail.

New accessories:

A 5/8" x 24" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 37° East, 22.2 feet.

A 5/8" x 24" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 35 1/2° East, 41.1 feet.

A 5/8" x 24" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 83° West, 20.8 feet. This accessory is located in East-West fence line.

A 3/4" brass washer, stamped "PLS 1106", nailed to the South side of a yellow barrel filled with rocks and supporting a fence, bears North 22° West, 19.4 feet. Brass washer is 1.5' above ground line.

Attached bearing object signs to rebar accessories. Nailed "witness" sign to fence corner post North of corner monument.

LOCATION AND COMMENTS: On steep hillside facing West, at fence corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 817088.83
E = 8717540.95

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/5N35R05

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-c