

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/01/05

CORNER DESIGNATION: 5N35, R-09, The Northeast Corner of Section 29.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 20, 21, 28, 29. Drove charred stake; dug pits & raised mound, as per instructions.

Record of Private Surveys Survey No. 27 states: "finding the original mrkd. cotton wood post, laying on the old Gov. mound under a East-West fence. I dig in the center of md. And find charred end of post over which I set a basalt stone 28"x8"x4", 18" in ground". Survey No. 106 reports finding the "old original post and stone in fence E & W".

**MONUMENT AND ACCESSORIES FOUND:**

Found 18"x14"x4" unmarked stone, lying flat, 12" under the ground in East-West fence line. This would be the stone from Survey No. 27 and recovered on Survey No. 106.

**MONUMENT MARKING DETAIL:**

T5N R35E  
S20|S21  
S29|S28  
2005  
PLS 1106

**MONUMENT SET:**

At position of found stone set a 2 1/2" brass cap on 2 1/2" x 30" galvanized iron pipe, 30" in the ground. Buried found stone on North side of monument, below ground. Cap marked as shown in Monument Marking Detail.

**New accessories:**

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" with cap 1" above ground level in fence line bears South 88° East, 21.0 feet.

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" with cap 1" above ground level in fence line bears South 88° East, 53.2 feet.

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" with cap 1" above ground level in fence line bears West, 25.2 feet.

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" with cap 1" above ground level in fence line bears West, 54.7 feet.

Attached bearing object signs to all rebar accessories. Nailed "witness" sign to railroad tie fence post 4' West of monument.

**LOCATION AND COMMENTS:** Corner is located in a fence line with fences East and West.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 817306.08  
E = 8722935.26


**FIRM:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

**COMPASS DECLINATION:** 18° East

Surveyor's Seal

**Witness:** Jason Wells, LSIT

/5N35R09



Renews 6/30/06

05-112-C