

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/24/05

CORNER DESIGNATION: 5N35, T-21, The East Quarter Corner of Section 26.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits; raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S26 | S25
2005
PLS 1106

MONUMENT SET:

I re-established this corner position on a line between the Northeast and Southeast corners of Section 26, holding a field line and berm running Easterly from the corner for latitude. At re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, marked as shown in Monument Marking Detail.

New accessories:

- A silver deep-1 magnet buried 20" in ground, bears North 41° East, 38.2 feet.
 - A purple deep-1 magnet buried 20" in ground, bears South 51° East, 49.9 feet.
 - A blue deep-1 magnet buried 20" in ground, bears South 34 1/2° West, 57.8 feet.
 - An orange deep-1 magnet buried 20" in ground, bears North 72° West, 53.9 feet.
- Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Corner located in a wheat field. There is a ditch and field berm extending East from the corner area.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 814529.44
E = 8739071.45

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35T21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-C