

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/21/05

CORNER DESIGNATION: 5N35, V-01, The Northwest Corner of Section 31.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 25, 36, 30 & 31, on side hill facing the E.; drove charred stake, dug pits and raised mounds as per instructions.

In record of Private Surveys, Survey No. 78, J.W. Kimbrell held the intersection of a sod fence running West 1/2 mile and North 1 mile and monumented with a stone 14 x 8 x 7.

Record of Survey No. 03-314-C found and held a railroad tie fence post for corner point.

**MONUMENT AND ACCESSORIES FOUND:**

Found railroad tie fence post with field line extending North and West as per Survey No. 03-314-C.

**MONUMENT MARKING DETAIL:**

T5N  
R34E R35E  
S25 | S30  
S36 | S31  
2005  
PLS 1106

**MONUMENT SET:** I held the railroad tie post at intersection of field lines North and West as best remaining evidence of the original corner location. At the South side of the railroad tie post, set 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe, 30" in the ground, marked as shown in Monument Marking Detail.

**New accessories:**

- A silver deep-1 magnet buried 20" below ground level, bears North 46° East, 49.9 feet.
  - A purple deep-1 magnet buried 20" below ground level, bears South 50° East, 55.2 feet.
  - A blue deep-1 magnet buried 20" below ground level, bears South 30° West, 54.2 feet.
  - An orange deep-1 magnet buried 20" below ground level, bears North 48° West, 55.6 feet.
- Buried bearing object signs with deep-1 magnets. Nailed "witness" sign to railroad tie North of corner monument.

**LOCATION AND COMMENTS:** Corner is located at a railroad tie fence post in farmed filed.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 811547.15  
E = 8712546.73



**FIRM:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

**COMPASS DECLINATION:** 18° East

Surveyor's Seal

Witness: Jason Wells, LSIT

/5N35V01



Renews 6/30/06

05-112-c