

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/01/05

CORNER DESIGNATION: 5N35, V-13, The Southeast Corner of Section 28.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 27, 28, 33 & 34; drove charred stake; dug pits & raised mound, as per instructions.

In Record of Private Surveys, Survey No. 106, the corner was recovered and noted as "the undisputed corner to Secs. 27-28-33 & 34". The survey does not indicate what was found or set to perpetuate the corner. Survey No. 182, reports identical dimensions to Survey No. 106.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
S28 | S27
S33 | S34
2005
PLS 1106

MONUMENT SET:

I held the intersection of Staggs County Road, a gravel road running East-West and a field berm running North as the best remaining evidence of the original corner position. At the corner point, set a 5/8" x 30" iron rebar with a 2" aluminum cap, with cap 8" below road surface, (corner falls in an area of heavy fill with large rocks). Cap marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap 1" above ground level bears North 53° East, 35.9 feet.

The centerline of a railroad track set vertically in the ground, protruding 2 feet above ground level bears South, 18.4 feet.

A blue deep-1 magnet buried 24" in ground bears South 41° West, 70.6 feet.

An orange deep-1 magnet buried 24" in ground bears North 50° West, 57.6 feet.

Buried bearing object tags with deep-1 magnets, attached bearing object tags to rebar accessory and vertical railroad track accessory. Set steel fence post 1 foot South of vertical railroad track accessory with "witness" sign attached.

LOCATION AND COMMENTS: Corner located at a point in the centerline of Staggs County Road and a field line running South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 811793.72
E = 8728512.83


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35NV13

Surveyor's Seal



RENEWS 6/30/06

05-112-C