

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/01/05

CORNER DESIGNATION: 5N35, X-13, The East Quarter Corner of Section 33.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

In Record of Private Surveys, Survey No 106, J.W. Kimbrell calls "the 1/4 sec. cor. bet. Secs. 33 & 34". Notes do not state what was recovered.

**MONUMENT AND ACCESSORIES FOUND:**

4-way field intersection with field berms running North, South, East and West.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1/4  
S33 | S34  
2005  
PLS 1106

**MONUMENT SET:**

I accept a 4 way field intersection with field berms running North-South and East-West as best remaining evidence of the original corner location. There is a vertical section of railroad track, leaning Southerly, here also. At the accepted corner position, set a 2 1/2" brass cap on a 2 1/2" x 30" iron pipe, 26" in the ground, cap marked as shown in Monument Marking Detail.

**New accessories:**

The base at ground level, of section of vertical railroad track protruding 3 feet above ground level and leaning Southerly bears South 80° West, 1.0 foot.

A silver deep-1 magnet buried 24" in ground bears North 51° East, 78.1 feet.

A purple deep-1 magnet buried 24" in ground bears South 42° East, 74.4 feet.

A blue deep-1 magnet buried 24" in ground bears South 46° West, 69.6 feet.

An orange deep-1 magnet buried 24" in ground bears North 45° West, 59.3 feet.

Buried bearing object signs with all deep-1 magnets. Set steel fence post with "witness" sign attached, 1 foot East of brass cap monument.

**LOCATION AND COMMENTS:** Corner located at 4 way field intersection, field lines North-South and East-West.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 809143.85

E = 8728513.55

**FIRM:** William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801


**COMPASS DECLINATION:** 18° East

**Witnesses:** Jason Wells, LSIT


Brian Cole

/5N35NX13

Surveyor's Seal



*William R. Wells*



Renews 6/30/06