

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 01/27/05

CORNER DESIGNATION: 5N35, Z-15, The South Quarter Corner of Section 34.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

Dave Krumbein, in Survey No. M-120-B, held road intersections for this corner point.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

SC  
T5N R35E  
1/4 S34  
2005  
PLS 1106

**MONUMENT SET:**

I held the intersection of centerlines of East-West Watts Road with York Road extending North, per Survey No. M-120-B. See Survey No. 02-021-C for additional information. At the re-established corner point, set a 2 1/2" brass cap on a 1 1/4 by 30" galvanized iron pipe with cap 10 inches below road surface, marked as shown in Monument Marking Detail.

**New accessories:**

The centerline of the base at ground level of a 2 1/2" diameter metal fence post bears North 87° East, 34.3 feet.

A 3/4" brass washer stamped "PLS 1106" 1.0 foot above ground level in PP&L pole #345002 bears South 87° East, 77.3 feet.

A 5/8" x 30" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", set flush with ground bears South 74° West, 69.8 feet.

A 3/4" brass washer stamped "PLS 1106" 1.0 foot above ground level in PP&L pole #344001 bears North 52° West, 65.7 feet.

Attached bearing object signs to rebar and power pole accessories. Set steel fence post with "witness" sign beside rebar accessory.

LOCATION AND COMMENTS: York Road runs North and a dirt field and Watts Road runs East and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 806448.79  
E = 8731202.44



FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Brian Cole

/5N35Z15



Renews 6/30/06