

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/03/05

CORNER DESIGNATION: 5N35, Z-17, The Southeast Corner of Section 34.

## PREVIOUS RENEWALS/SURVEYS ETC.:

Originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865.  
Notes state: Set post Standard Cor. for Secs. 34 & 35, on level, drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

## MONUMENT MARKING DETAIL:

SC  
T5N R35E  
S34 | S35  
2005  
PLS 1106

## MONUMENT SET:

Re-established corner on parallel of latitude by single proportion measurement between the Standard South one-quarter corners of section 34 and 35. A re-established corner position, set a 2 1/2" brass cap on a 2 1/2" by 30" galvanized iron pipe with cap 20" below ground surface, marked as shown in Monument Marking Detail. Corner falls in a wheat field, 20' North of a dirt field road.

### New accessories:

A silver deep-1 magnet, buried 20" in the ground, bears North 56° East, 47.8 feet.

A 3/4" brass washer stamped "PLS 1106", 1.0 foot above ground level in PP&L pole #021801, bears South 81° East, 199.7 feet.

A 3/4" brass washer stamped "PLS 1106", 1.0 foot above ground level in PP&L pole #020802, bears South 70° West, 48.0 feet.

An orange deep-1 magnet buried 20" in the ground, bears North 45° West, 45.1 feet.

Buried bearing object signs with deep-1 magnets. Attached bearing object signs to power pole accessories.

LOCATION AND COMMENTS: Monument is 20 feet North of a dirt field road in a farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 806426.42  
E = 8733846.70


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Brian Cole

/5N35Z17



RENEWS 6/30/06

05-112-c