

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/18/08

CORNER DESIGNATION: Z-11, The South Quarter Corner of Section 33, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post on level. Drove charred stake; dug pits & raised mound, as per instructions. John Kimbrell, in his survey recorded at Book 1, Page 402, Record of Private Surveys, reestablished the corner and set a stone, 20 x 10 x 8. Steve Haddock, under Survey No. 08-039-C, calculated a position for this corner at the intersection of the centerline of Whiteman Road with the field berm extending South.

MONUMENT AND ACCESSORIES FOUND: None. There is a old established field line and berm, extending South, from the corner point. Field line and berm show on the 1956 ASCS aerial photography.

## MONUMENT MARKING DETAIL:

T6N R36E  
1 S33  
4 S4  
T5N  
2008  
PLS 1106

MONUMENT SET: I reestablished this corner point at the intersection of the centerline of Whiteman Road with an old field berm extending South, (see Survey No. 08-039-C). At the reestablished corner point, set 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 9" below road level, marked as shown in "Monument Marking Detail".

New accessories:

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 67 1/2° East, 40.3 feet.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 60 1/2° East, 40.9 feet.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 03° East, 24.1 feet.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 58 1/2° West, 29.0 feet.

Wired witness sign to group of rods at the North end of field berm, South of corner.

Attached bearing object signs are attached to the rebar accessories.

LOCATION AND COMMENTS: Corner is located at the intersection of Whiteman Road with a field berm extending South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 839067.94  
E = 8756754.34


FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36Z11



*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Expires 6-30-10

09-10-c