

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/11/05

CORNER DESIGNATION: 5N35, J-25, Northeast Corner of Section 13.

PREVIOUS RENEWALS/SURVEYS ETC.: Originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 12, 13, 7 & 18; from which:

- A balm, 10 ins. diam., brs. N.34°E., 81 lks. dist.
- A balm, 6 ins. diam., brs. N.62°W., 97 lks. dist.
- A balm, 6 ins. diam., brs. S.36°15'W., 124 lks. dist.
- A balm, 7 ins. diam., brs S.45°30'E., 117 lks. dist.

Krumbein recovered a 2" iron pipe and remonumented with the existing brass cap monument in 1981. This corner monument has been used on all surveys in the area since 1981.

MONUMENT AND ACCESSORIES FOUND:

A 2 1/2" brass cap on a 2 1/2" iron pipe protruding 14" from a large rock mound. Cap marked as shown in Monument Marking Detail. A steel fence post is located 2 feet South of monument.

MONUMENT MARKING DETAIL:

T5N
S12 | S7
R35E S13 | S18 R36E
1980
PLS 933

MONUMENT SET:

Maintained existing monument by establishing new accessories:

A 3/4" brass washer stamped "PLS 1106" 1.0 feet above ground level in railroad tie fence post bears North 26° East a distance of 42.7 feet.

A 3/4" brass washer stamped "PLS 1106" 1.0 feet above ground level in railroad tie fence post bears South 79° East a distance of 27.5 feet.

The centerline at ground level of a 4" gas line paddle 1.0 feet above ground level bears South 13° East a distance of 139.7 feet.

"XBO" chiseled in a 30" x 24" x 18" rock bears North 20° West a distance of 26.8 feet, measured to "X".

Attached "witness" sign to steel fence post 2 feet South of corner. Nailed bearing object signs to the railroad tie fence posts containing brass washers.

LOCATION AND COMMENTS:

Corner located in levee East the Walla Walla River.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 827688.48
E = 8743558.56



FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witness: Jason Wells, LSIT

5N35J25



RENEWS 6/30/06

05-112-C