

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

One-quarter corner common to Sections 11 & 12,  
Township 5 North, Range 37 East, of the Willamette Meridian,  
Umatilla County, Oregon.


G-21

History of original corner establishment:

SLO,  
George Williams, Deputy Surveyor, Contract No. 176,  
20 July, 1872.  
"Set post for 1/4 Sec. Cor. from which:  
A White Fir 10 in. dia. bears N80°W 11 lks. dist.  
A White Fir 4 in. dia. bears N67°E 14 lks. dist."

Description of evidence found:

A diligent search was performed for the original monument or its accessories. I found an ancient fence corner at this position for which I have testimony of its origins being at least sixty years ago. I could find no evidence of the original monument or its accessories. I consider the ancient fence corner to be the best evidence of the original corner, and monumented this position.



Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner of an ancient fence bearing S89°58'15"W into this position, and another ancient fence bearing S1°21'55"E out of this position, I set a 1" standard "Hotpland" galvanized iron pipe with 2-1/2" dia. Bronze cap marked as shown, from which:

A 16 in. dia. Douglas Fir bears N60°30'E, a distance of 12.85 feet to center, with face mkd. "1/4S12BT". An Aluminum nail is driven into a 3/4" Brass washer mkd. "WA 25849 OR 2360" set in the center of the "B" on face which is typical for all Bearing Trees marked on this restoration.

A 12 in. dia. Grand Fir bears S56°E, a distance of 38.05 feet to center, with face mkd. "1/4S12BT".

An 11-1/2 in. dia. Grand Fir bears S37°W, a distance of 27.41 feet to center, with face mkd. "1/4S11BT".

An 8 in. dia. Western Larch bears N79°30'W, a distance of 21.24 feet to center, with face mkd. "1/4S11BT".

I affixed Umatilla County Surveyor Yellow Metal Bearing Object signs to these Bearing Trees. I also affixed Bearing Tree signs (penalty for disturbance, etc.) to each tree.

Bearings are magnetic, using a declination of 19°E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Paul W.P. Tomkins*

OREGON  
JULY 26, 1988  
PAUL W.P. TOMKINS  
2360

8/25/92

RECEIVED BY

Umatilla County Surveyor

Date 9-92

Rec'd By JK

No. 92-106-C

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_, I hereby certify that the within instrument was  
filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)