


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. B-9

History of original corner establishment: No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner: At surveyed point set 1"x30" galvanized pipe with 3" brass cap stamped:


Set pipe 24" in ground.

Bearing trees:

A Blue Spruce 6" in dia bears N80°E 37.5 ft scribed 1/16 S4 80 BT.

A: Blue Spruce 8" dia bears S34°E 41.8 ft scribed 1/16 S4 80 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red.



I hereby certify the above corner monument was established as herein described on Sept. 18, 1980.

Witnesses: R. Orton, G. Wagoner, L. Huntsman, A. Hanley



Office of... County Surveyor... Umatilla... Oregon... State of... I hereby certify that the within instrument was filed in this office for record on the... day of... 19... David Krumbein by Betty Shatto