


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. C-11

History of original corner establishment: No corner was originally set.



Description of corner evidence found:


Description of monument and accessories | established to perpetuate the original location of this corner: At surveyed point set 1"x30" galvanized pipe with 3" brass cap stamped:

Set pipe 24" in ground from which:

A White Fir 21" dia bears N39°E 55.3 ft. scribed: C $\frac{1}{4}$ S4 BT.

A White Fir 15" dia bears S34°E 43.6 ft scribed: C $\frac{1}{4}$ S4 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washers stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red.



I hereby certify the above corner monument was established as herein described on Sept. 19, 1980.

Witnesses: R. Orton
G. Wagoner
L. Huntsman
A. Hanley

Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of.....December....., 1980
 David Krumbein by Betty Shatto
 (COUNTY OFFICIAL) (DEPUTY)