


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. C-13


**History of original corner establishment:** The original surveyors George R. and William S. Campbell under GLO Contract No. 699, 1899, set on summit of divide between Mill Creek and Walla Walla River; 750 ft above sec cor bears N80°E & S80°W, set a yew post, 3 ft long 3 in. square 24 ins in ground for ¼ sec cor marked ¼S on W face from which:  
 A Fir 28" dia bears N40°E, 28 lks dist marked ¼ S3 BT;  
 A Fir 20 ins. diam bears N59°W, 44 lks dist marked ¼ S4 BT.



**Description of corner evidence found:** At corner location found rotted stump with pieces of old blaze in it and part of "¼" visible for N.E. BT. Found old partially rotted stump with part of blaze attached and part of "¼" visible. At intersection of record distances from found stumps searched for remains of old yew post. Could find no trace of original post. Establish a point by measuring record distance from original BT stumps.

**Description of monument and accessories | established to perpetuate the**

**original location of this corner:** At intersection point set 1"x30" pipe with 3" brass cap stamped: Set pipe 24" in ground with mound of stone and dirt to cap.



**Bearing Trees:**

Old: A Fir stump 34" diam bears N40°E, 18.5 ft with piece of blaze and part of "¼" visible,  
 A Fir stump 30" dia bears N60°W 29.0 ft with part of blaze and "¼" visible.

New: A White Fir 9" dia bears S79°E, 61.8 ft scribed ¼ S3 BT  
 A White Fir 11" dia bears S39° W, 58.5 ft scribed ¼ S4 BT

Attached 54-3 & 54-4 signs on all BT's. Attached brass washer stamped LS 1294 to foot blaze of new BT's. Painted blazes & 6" band around new BT's red.



I hereby certify the above corner monument was re-established as herein described on Sept. 3, 1980.

Witnesses: R. Orton  
 L. Huntsman

Office of.....County Surveyor..... County of..... Umatilla  
 Oregon  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... December....., 1980  
 David P. Humbein..... by Betty Shatto  
 (COUNTY OFFICIAL) (DEPUTY)