


CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Index File No. C-5

History of original corner establishment: In 1872, under GLO Contract No. 176, George Williams set a Fir post for 1/4 sec cor. From which:
A Tamarack 12" dia bears N83°W 29 lks.
A Spruce 10" dia bears N80°E 40 lks dist



Description of corner evidence found: Found: A windfallen snag 20" dia with visible scribing "4 S5". Snag has an old cruiser tag date 1956.

Description of monument and accessories established to perpetuate the original location of this corner: Set from root hole of original Spruce a 1"x30" galvanized pipe with 3" brass cap. Pipe set S80°W 26.4 ft. Brass cap stamped: Set pipe 24" in ground.
Bearing Trees:
A White Fir 12" dia bears N79°E 48.2 ft scribed 1/4 S5 BT.
A White Fir 6" dia bears S2°W 10.1 ft scribed 1/4 S6 BT.
Attached 54-3 & 54-4 signs to both BT's.
Attached brass washers stamped LS 1294 to foot blaze of both BT's.
Painted blazes and 6" band around both BT's red.



I hereby certify the above corner monument was re-established as herein described on Sept. 23, 1980.

Witnesses: R. Orton
G. Wagoner
L. Huntsman
A. Hanley

Office of..... County Surveyor..... County of..... Umatilla
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of December, 1980
David Brumbein by Betty Hatt
(COUNTY OFFICIAL) (DEPUTY)