

USDA-FOREST SERVICE

Index File No. C-9

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 5N R. 38E R.D. W² County UMATILLA

Merid. WILL N.F. UMATILLA State OREGON

CORNER DIAGRAM



Description of corner evidence found:

After a thorough search no evidence of the post or BT could be found.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
Howard L. Perry

Title
PLS 1294

Division
10/80

Headquarters
Date
7100-52-(3,68)

CORNER RECORD (PERPETUATION)

Description of monument and accessories established to perpetuate the original location of this corner:

Set at proportioned point 1"x30" pipe with 3" brass cap stamped:

Set pipe 24" in ground.

CROWN ZELLERBACH
T5N R38E

T5N R38E

1
4

S4

1980

OR

PLS 1294

Bearing Trees:

A White Fir 12" dia. bears S49°E 92.2 ft., scribed 1/4 S4 BT.

A Spruce 11" dia. bears N29°E 30.8 ft., scribed 1/4 S4 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.

Work Done By _____ Title _____ Date _____ State Registration No. _____
or Agency _____

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No. T. R. M. Tract or Surv. No. Cor.

C-9 5N 38E

WEST 1/4 SEC. 4 TSN R38E

C-96

ORIG SURVEY BY CAMPBELL IN 1899

SEARCH AREA LOCATED BY MEASUREMENT
FROM EVIDENCE PIT $\frac{5}{8}$

NO EVIDENCE FOUND, ALTHOUGH THERE
ARE SEVERAL TREES AND STUMPS IN THE AREA
WITH SIGNS OF AXE-WORK. AREA HAS BEEN LOGGED
AND RE-LOGGED.

5-29-80

David J. Langley ORLS 1099
GREG ORTON

COMPASS DECL. $19\frac{1}{2}^{\circ}$ EAST

US
INC
FIC
T

Meas
COR

↑ N ↓

PHC
PHC
FIC
Obj
Ide
PLA
Sto
X -
Y -
Est