


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-9b

History of original corner establishment: The original surveyor William E Campbell under GLO Contract No. 699, 1899, set a basalt stone 12x10x8 ins 8 ins deep in the ground for closing corner for sections 4 & 9, marked CC on the East face, with 5 grooves on the South face, from which:

A Spruce 15" dia bears N71 $\frac{1}{2}$ ⁰E, 13 lks dist marked T5N R38E S4 BT.
A Fir 22" dia bears S50 $\frac{1}{4}$ ⁰E 61 lks dist marked T5N R38E S9 BT.



Description of corner evidence found: Original basalt stone with "CC" chiseled marks on top and 5 notches on Easterly edge, loosely set and generally agreeing with record size, with a 3/4" iron pipe firmly set along South side of stone. We assume stone to be disturbed. Established position from remains of original bearing trees. An original 15" Spruce now a 30" rotting snag approx 6" tall with evidence of an old scar bears N71 $\frac{1}{2}$ ⁰E 78 ft. and an original 22" Fir now a 30" well decayed stump with visible scribing "s" on partially overgrown blaze bears S50 $\frac{1}{4}$ ⁰E 40.3 ft. The original stone and I. pipe bear S76⁰W 1.5 ft.


Description of monument and accessories established to perpetuate the original location of this corner: Set in place of original stone 1"x30" galvanized pipe with 3" brass cap stamped:

Set pipe 24" in ground with original stone buried along side.

Bearing trees:

A White Fir 18" dia. bears S68⁰E 82.4 ft scribed T5N R38E S9 BT.
A White Fir 16" dia bears N66⁰E 68.1 ft scribed T5N R38E S4 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washers stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red.



I hereby certify the above corner monument was re-established as herein described on Sept. 23, 1980.

Witnesses: R. Orton
G. Wagoner
L. Huntsman
A. Hanley



Office of..... County Surveyor..... County of..... Umatilla
Oregon
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of..... 19.....
..... by.....
(COUNTY OFFICIAL) (DEPUTY)

R-186-B