


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. F-7

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 1"x30" Galvanized Pipe with 3" brass cap stamped:


Set pipe 22" in ground with mound of stone and dirt to cap.

New BTs:

A White Fir 22" dia. bears S36°E, 52.3 ft., scribed CN 1/16 S8 BT.

A Spruce 6" dia. bears N85°W, 45.7 ft., scribed CN 1/16 S8 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was established as herein described on October 27, 1980.

Witnesses: R. Orton
A. Hanley

Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of.....December.....1980.....
 David Krumbein by Betty Shatto
 (COUNTY OFFICIAL) (DEPUTY)