


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-13

History of original corner establishment:

In 1899 under GLO Contract No. 699, William E. Campbell set a Fir tree 24" in dia. for 1/4 corner, scribed 1/4 S on West side from which:

- A Fir 24" dia. bears S24°E 54 lks. scribed 1/4 S10 BT.
- A Fir 20" dia. bears N52½°W 49 lks. scribed 1/4 S9 BT.



Description of corner evidence found:

Rotted stump of original Fir corner tree flush with ground, dia. approx. 18" to 20". No marks remaining from which:

A Fir 24" dia. now a 28" shattered stump approx. 3' tall with visible scribing "1/4 BT" on partially healed face bears S24°E 37.9 ft. No evidence of original NW BT.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set in place of 24" tree a 1"x30" pipe with 3" brass cap stamped:

Set pipe 24" in ground with mound of stones to cap.
From which:


- A Fir 16" dia. bears S69°E 14.0 ft., scribed: 1/4 S10 BT.
- A Fir 13" dia. bears N11°W 26.1 ft., scribed: 1/4 S9 BT.

Attached 54-4 and 54-3 signs to both BTs. Attached brass washers stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was reestablished as herein described on October 7, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wyatt
A. Hanley



Office of..... County Surveyor..... County of..... Umatilla
Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of..... December..... 19..... 80
David P. Rumber..... by..... Betty Shatto.....
(COUNTY OFFICIAL) (DEPUTY)