


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-9a

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set a 1"x30" pipe with a 3" brass cap stamped:

Set corner 24" in ground. No stones for mound.

From which:

A White Fir 12" dia. bears S25°W 20.0 ft., scribed: S 1/16 S8 BT.


A White Fir 18" dia. bears N55°W 31.8 ft., scribed: S 1/16 S8 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was established as herein described on September 25, 1980.

Witnesses: R. Orton
G. Wagoner
L. Huntsman
A. Hanley



Office of..... County Surveyor..... County of..... Umatilla
 Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... December....., 19...80
 David Huntsman by Betty Skatto
 (COUNTY OFFICIAL) (DEPUTY)