


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-6a

History of original corner establishment:
No corner was originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 1"x30" galvanized pipe with 3" brass cap stamped:

Set pipe 26" in ground from which:

A Spruce 8" in diameter bears N65°E 16.3 ft.
scribed: W 1/16 S8 BT


A Tamarack 6" in diameter bears N16°W 42.5 ft.
scribed: W 1/16 S8 BT

Attached 54-3 & 54-4 sings to both BT's.
Attached brass washers stamped LS 1294 to
foot blaze of both BT's. Painted blazes
and 6" band around both BT's Red.

CROWN ZELLERBACH
T5N R38E
W 1/16 | S8
1980
OR PLS 1294

I hereby certify the above corner monument was established as herein described on November 11, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wagoner



Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of..... 19.....
David Kumbier by *City Shatto*
(COUNTY OFFICIAL) (DEPUTY)