

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-7a


History of original corner establishment:

In 1872, under G.L.O. Contract No. 176, George Williams set a post from which:

A Spruce 14" dia. bears N 17 lks.

A Fir 8" dia. bears S18°E 12 lks.

Resurvey by George R. and William E. Campbell under G.L.O. Contract No. 699, 1899 found corner and BTs set by Williams.



Description of corner evidence found:

A diligent search was made and no evidence of original post or BTs could be found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At proportioned point set 1"x30" Galvanized Pipe with 3" brass cap stamped:


Set pipe 22" in ground and built mound of dirt and stone to cap.

From which:

A Spruce 6" dia. bears N25°E 60.6 ft., scribed: 1/4 S8 BT.

A Tamarack 7" dia. bears N33°W 94.9 ft., scribed: 1/4 S8 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washers stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was reestablished as herein described on November 10, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wagoner

Office of.....County Surveyor..... County of.....Umatilla.....
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of.....December....., 19..80
.....David..... by.....Betty Shatto.....
(COUNTY OFFICIAL) (DEPUTY)