


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-9c

History of original corner establishment:

The original surveyor, William E. Campbell, under GLO Contract No. 699, 1899, set a point 50' below the S.E. corner Sec. 8 and set an ironstone 24x12x6 ins. 18" deep in the ground for the N.E. corner, Sec. 17, marked with 4 notches on the East edge.



From which:

A Fir 6" dia. bears S4½°W 1 chain 28 lks. dist. marked T5N R38E S17 BT.

Description of corner evidence found:

Original stone, firmly set with 4 distinct notches on East edge, from which:

The original bearing tree, now a 26" Douglas Fir, alive and in good condition, previously opened partially by chainsaw and axe, but not to scribed face, bears S16½°W 84.5 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

At corner location set a 1"x30" Galvanized Pipe with 3" brass cap stamped:

Set pipe 20" in ground with original stone buried alongside. Built mound of stone to cap.

From which:

The original Bearing Tree:

A 26" dia. Douglas Fir bears S16½°W 84.5 ft.

A Bearing Object:

A large boulder protruding forth from the mountain (10'x15') marked "BO" about 3½ ft. above the ground. BO is marked on farthest N.E. face of the rock. Rock is mostly round in shaped "X" bears S44°W 14.1 ft.

CROWN ZELLERBACH

T5N R38E
S17
1980
OR PLS 1294



I hereby certify the above corner monument was reestablished as herein described on October 8, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wyatt
A. Hanley

Office of.....County Surveyor..... County of.....Umatilla.....
Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of.....December..... 1980
David R. Chambers by Betty Slatts
(COUNTY OFFICIAL) (DEPUTY)