


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

George S. Pershin under Contract No. 362 dated August 2, 1880:

Set Basalt Stone 12 X 10 X 5 from which

Pine, 12" Dia., BRS. N48°W, 41 Lks. Dist.
Pine, 11" Dia., BRS. N74°E, 60 Lks. Dist.



Description of corner evidence found:

Found no original evidence.

Description of monument and accessories established to perpetuate the original location of this corner

Proportionate point for corner falls in Rd.; unable to bury iron pipe.
Set 7" railroad spike 2" below surface of Rd. from which
32" X 2" iron pipe with brass cap marked:
BRS. N45°W, 10.0 Ft. Dist.

T5S R29E
S35 SC
RM
1979
PLS 346

Douglas Fir, 10" Dia., BRS. N14½°W., 24.4 Ft. Dist.
Marked: T5S R29E S35 SC BT

Ponderosa Pine, 8" Dia., BRS. N32½°E., 46.6 Ft. Dist.
Marked: T5S R29E S36 SC BT

6' Iron Fence Post with "Survey Monument" sign within 5' of corner.

All B.T. have BT tag and painted red stripe, New BTs have brass washer stamped: PLS 346; nailed to lower blaze.

Office of County Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the day of
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 10-17-79
Rec'd By msj
No. A-1171-B

