


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430.

Surveyor General Record States:

Set Basalt stone 12x8x7 ins. for corner to Sections 34-35-2-3. Marked with 4 notches on the West and 2 notches on East edges.

- A 26" Pine bears N71E, 109 lks.
- A 14" Pine bears S14E, 126 lks.
- A 24" Pine bears S38W, 147 lks.
- A 20" Pine bears N50W, 126 lks.



2-17

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found stone, call size, properly marked in a mound of stone, from which:

Original BTs


- A 26" Pine stump bears N71E, 72.4 ft., scribes visible.
- A 20" Pine, good condition, bears S19E, 83.0 ft., scribes visible.
- A 34" Pine, good condition, bears S33W, 98.2 ft., scribes visible.
- A 18" Pine, good condition, bears N50W, 83.4 ft., scribes visible.

Description of monument and accessories established to perpetuate the original location of this corner

At position of stone, I set 2 1/2"x30" iron pipe with brass cap marked as shown, 24" in ground, raised mound of stone, 5 ft. at base to top of cap, from which:

New BT

- A 18" Pine bears N83E, 52.7 ft. marked T4S R30E S35 BT.
- Buried stone north and alongside pipe.
- Nailed brass washer in BT blaze.
- Set steel fence post 5 1/2 ft. North of corner.
- Used steel tape and magnetic compass with 20° E declination.
- Measured to face of blaze on original BT and center of new BTs.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 13th day of Aug, 1974, at o'clock m., (signed)
Ralph Thompson by
(COUNTY OFFICIAL) (DEPUTY)

Q-15-R