


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

History of original corner establishment: Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430.



Surveyor General Record States:

Set basalt stone 18 x 10 x 5 ins. for cor. to sect's. 31-32-5-6 marked with 5 notches on E & 1 notch on West edges. From which:

- A 8" Pine bears N 36 E, 134 lks.
- A 28" Pine bears S 70 E, 179 lks.
- A 24" Pine bears S 54 W, 102 lks.
- A 20" Pine bears N 78 W, 102 lks.

2-5

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found stone, call size properly marked, firmly set in a mound of stone, from which:

Original BTs

- A 44" Pine, good condition, bears S68E, 118.1 ft., scribes visible.
- A 30" Pine, dead, bears S51W, 75.0 ft., scribes visible.
- A 22" Pine, dead and down, bears N76W, 75+ ft., scribes visible.

No evidence of other ET.

Description of monument and accessories established to perpetuate the original location of this corner

In position of stone, I set 2½"x30" iron pipe with brass cap, marked as shown 22" in ground. Raised mound of stone 6 ft. on base to top of cap, from which:

New BTs

- A 24" Pine bears N16E, 44.4 ft. marked T4S R30E S32 BT.
- A 9" Pine bears S65W, 31.7 ft. marked T5S R30E S6 BT.
- A 13" Pine bears N40W 15.0 ft. marked T4S R30E S31 BT.

Nailed brass washer to BT blaze.

Buried original stone East and along side pipe.


Set steel fence post 5+ ft. West of corner.

Used steel tape and magnetic compass with 20° E declination.

Measured to face of blaze on original BTs and center of new BTs.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Duane J. Griffith*  
**OREGON  
JULY 10, 1974  
DUANE J. GRIFFITH  
644**



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 13 day of April, 1974, at ..... o'clock ..... m., (signed)  
Ralph J. ... by ..... (DEPUTY)  
 (COUNTY OFFICIAL)

S-69-M I-111-R 5