


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record States:

Set post for cor. to Sect's. 2-3-10-11, From which:

- A 12" Tamarack bears N 61 E, 61 lks.
- A 24" Tamarack bears S 47 W, 29 lks.
- A 20" Tamarack bears N 40 W, 37 lks.
- A 12" Fir bears S 50 E, 10 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original BTs as follows:

- A 8" Tamarack snag bears N29E, 40.0 ft., scribes visible.
- A 17" Fir snag bears S75E, 6.6 ft., blaze healed.
- A 30" Tamarack, good condition, bears S28W, 22.7 ft., scribes visible.
- A 32" Tamarack, good condition, bears N53W, 24.4 ft., scribes visible.

Description of monument and accessories established to perpetuate the original location of this corner

At corner point, based on record distance to BTs, I set 2½"x30" iron pipe with brass cap marked as shown, 24" in ground, from which:

New BTs


- A 13" Fir bears N41E, 67.0 ft. marked T5S R30E S2 BT.
- A 12" Fir bears S59E, 68.5 ft. marked T5S R30E S11 BT.

Nailed brass washer to BT blaze.
 Set steel fence post 5+ ft. South and 5+ East of corner.
 Corner is approximately 6 ft. South of small creek.
 Used steel tape and magnetic compass with 20° E declination.
 Measured to face of blaze of original BTs and center of new BTs.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Duane J. Griffith

OREGON
 JULY 10, 1974
 DUANE J. GRIFFITH
 644



Office of Surveyor County of Wasatch
 State of Utah, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of Aug, 1974, at o'clock m., (signed)
Ralph Thompson by
 (COUNTY OFFICIAL) (DEPUTY)

E-11
J-113R 10