

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


E-21

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record States:

Set basalt stone 16 x 10 x 10 ins. for cor. to Sect's. 1-2-11-12, marked with 5 notches on S & 1 notch on E edges, From which:

- A 30" Pine bears S 55 W, 98 lks.
A 18" Pine bears N 62 W, 63 lks.
A 20" Pine bears S 66 E, 56 lks.
A 18" Pine bears N 63 E, 115 lks.



No record of subsequent remonumentation was found in County Records. Description of corner evidence found:

Found original stone, call size, properly marked in a rock jack 20' West of corner. Found original trees as follows;

- A 18" Pine, good condition, bears N68E, 75.9 ft., scribes visible.
A 33" Pine, good condition, bears S62E, 37.0 ft., scribes visible.
A 36" Pine, good condition, bears S61W, 64.7 ft., scribes visible.
A 22" Pine, poor condition, bears N53W, 42.0 ft., scribes visible.


Description of monument and accessories established to perpetuate the original location of this corner

At corner point, based on BTs, I set 2 1/2"x30" iron pipe with brass cap marked as shown, 22" in ground, raised mound of stone 7 ft. at base to top of cap, from which:

New BT

A 27" Pine bears N63W, 77.0 ft. marked T5S R30E S2 BT.

Nailed brass washer to BT blaze. Buried original stone South and along side pipe. Set steel fence post 5+ ft. South of corner. Used steel tape and magnetic compass with 20° E declination. Measured to face of blaze of original BTs and center of new BTs.



Office of Surveyor County of Humboldt
I hereby certify that the within instrument was filed in this office for record on the 13 day of May, 1974, at 10 o'clock a.m., (signed)
[Signature] by [Signature] (DEPUTY)

E-21

S-637115