


G-6

① History of original corner establishment:
Corner not previously established.



② Description of corner evidence found:
N.A.

③ Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv iron pipe with 3" brass cap 24" in the ground. Stamped brass cap as shown in the diagram.

From which:

A lodge pole pine 10" dia. bears N 61 W, 29.4 ft. scribed C W 1/16 S8 BT.

A " " " 5" dia. Bears S 29 E, 4.3 ft. " " " " "

Nailed brass washers stamped PLS 848 & each bearing tree signs to each tree, painted red band around each tree.

Set steel posts with warning & bdry. signs, 5' S & 5' W.

Bearing-True Solar Grid

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witness to above corner.

L. Wyllie

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 20 day of JANUARY, 1901
David H. Klein by _____
(COUNTY OFFICIAL) (DEPUTY)

G-6