

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


J-13

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record states:

Set basalt stone 15 x 10 x 9 in for corner to Section 9-10-15-16. Marked with 4 notches on South and 3 notches on the East edges, from which:

- A 23" Pine bears N30W, 75 lks.
- A 13" Pine bears N80E, 29 lks.
- A 30" Pine bears S38W, 70 lks.
- A 30" Pine bears S50E, 15 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:
Found stone, call size properly marked in a mound of stone, from which:

Original BTs

- A stump hole bears N80E 19+ ft.
- A 3/4" Pine, good condition, bears S50E, 9.9 ft., scribes visible.
- A 30+'' Pine stump bears S38W, 51.5 ft., BT visible.
- A 32'' Pine, good condition, bears N30W, 49.5 ft., scribes visible.

Description of monument and accessories established to perpetuate the original location of this corner
In position of stone, I set 2 1/2"x30" iron pipe with brass cap marked as shown 25" in ground, from which:


New BTs

- A 15" Fir bears N49E, 27.7 ft. marked T5S R30E S10 BT.
- A 8" Pine bears S72W, 71.6 ft. marked T5S R30E S16 BT.

Nailed brass washer in BT blaze.
Buried stone South and along side pipe.
Set steel fence post 5+ ft. East of corner.
Raised mound of stone 5 ft. at base to top of cap.
Used steel tape and magnetic compass with 20° E declination.
Measured to face of blaze on original BTs and center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane I. Griffith
OREGON
JULY 10, 1966
DUANE I. GRIFFITH
644



Office of *Surveyor* County of *Umatilla*
State of *Oregon*, I hereby certify that the within instrument was filed in this office for record on the *13* day of *April*, 19 *74*, at *11* o'clock *am*, (signed) *Duane I. Griffith* by *_____* (DEPUTY)

J-13