


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record States:

Set basalt stone 13 x 8 x 7 ins. for $\frac{1}{4}$ cor. marked $\frac{1}{4}$ on N face. From which:

A 40" Pine bears S 70 W, 139 lks.
A 10" Pine bears N 60 E, 249 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, call size marked $\frac{1}{4}$, 10" in the ground, from which:

Original BT

A 40" Pine snag bears S70W, 89.0 ft., scribes visable.

Found no evidence of other BT.

Description of monument and accessories established to perpetuate the original location of this corner

In position of stone, I set $2\frac{1}{2}$ "x30" iron pipe with brass cap marked as shown, 22" in ground, raised mound of stone 6 ft. at base to top of cap, from which:

New BTs

A 9" Pine bears N38W, 55.4 ft. marked $\frac{1}{4}$ S12 T5S R30E BT.
A 10" Pine bears S60W, 33.1 ft. marked $\frac{1}{4}$ S13 T5S R30E BT.

Nailed brass washer to BT blazes.

Corner of fences running South and West bears N30E, 6.0 ft.

Buried original stone North and along side pipe.

Set steel fence posts 5+ ft. South and 5+ ft. West of corner.

Used steel tape and magnetic compass with 20° E declination.

Measured to face of blaze on original BT and center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane I. Griffith
OREGON
JULY 10, 1964
DUANE I. GRIFFITH
644

T 5S R 30E
S 12
 $\frac{1}{4}$ S 13
1974
PLS 644

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 13 day of Aug, 1974, at o'clock m., (signed)
Ralph Thompson (COUNTY OFFICIAL) (DEPUTY)

*J-23
I-123R*