

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


J-5

History of original corner establishment:

Corner established in 1883, by F.W. Campbell under General Land office Contract No. 486 Surveyor general records state: Set basalt stone 17x9x5 ins. 11ins. in ground for corner to sections 7,8,17,& 18 marked with 4 notches on S and 5 notches on E edges.

From which:

- A pine 8" dia. bears S 67 E 231ks dist. marked T5S R30E S17 BT.
A pine 10" dia. bears N 51 E 60 lks dist. marked T5S R30E S 8 BT.
A fir 8 ins. dia. bears S 57 W 651ks dist. marked T5S R30E S18BT.
A tamarack 6ins. dia. bears N 56 W 131ks dist. marked T5S R30E S7 BT.



Description of corner evidence found:

After a thorough search of the area no evidence is found. It appears that adjacent road construction & logging have destroyed all traces of the corner. Therefor set position by proportion.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 3"x30" galv iron pipe with 3" brass cap 20" in the ground & raised a mound of stone around pipe. Stamped brass cap as shown in the diagram.

From Which:

- A fir 12" dia. bears N 51 42' E 63.5 ft. scribed T5S R30E S8 BT.
A fir 12" dia. bears S 61 40' W 65.0 ft. Scibed T5S R30E S18 BT.
A fir 12" dia. bears S 55 30' E 21.2 ft. " " " S17 "
A steel post bears N 48 W 6.0 ft. with warning & bearing tree signs attached.
Painted red band around each tree.
Bearing solar grid.

Note: No trees available in section 7.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1968 DOUGLAS M. FERGUSON 848

Witness to above corner.

D.Herburger
L.Wyllie

Office of... Surveyor... County of... Umatilla...
State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the... 26... day of... January... 1981
David H. Kila (COUNTY OFFICIAL) by (DEPUTY)

J-5

S-63-M