


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468



Surveyor General Record States:

Set basalt stone 15 x 10 x 6 for Cor. to Sects. 15-16-21-22 marked with 3 notches on S & E edges, From which:

- A 30" Pine bears S 10 W, 75 lks.
- A 30" Pine bears S 20 E, 98 lks.
- A 20" Pine bears N 42 E, 134 lks.
- A 30" Pine bears N 9 W, 225 lks.

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, call size, properly marked in mound of stone, from which:

Original BTs

- A 30" Pine, good condition, bears N42E, 89.4 ft., scribes visible.
- A 28" Pine, good condition, bears S20E, 65.5 ft., scribes visible.
- A 28" Pine, good condition, bears S10W, 50.2 ft., blaze healed.
- A 30" Pine stump bears N9W, 151.4 ft., no scribes visible.


Description of monument and accessories established to perpetuate the original location of this corner

In place of stone, I set 2 1/2" x 30" iron pipe with brass cap marked as shown, from which:

New BT

A 12" Pine bears N18W, 16.4 ft. marked T5S R30E S16 BT.

Nailed brass washer to BT blaze.
Buried stone North and along side pipe.
Set steel fence post 5' North of corner.
Used steel tape and magnetic compass with 20° E declination.
Measured to face of blaze on original BTs and center of new BT.



Office of Surveyor County of Wasatch
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 15th day of Aug; 1974, at o'clock m., (signed)
Ralph Thompson by
 (COUNTY OFFICIAL) (DEPUTY)

N-13

I-25-R