


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-7 1/4

History of original corner establishment:  
Corner not previously established.



Description of corner evidence found:

N.A.

Description of monument and accessories | established to perpetuate the original location of this corner:

Corner falls on edge of 5312 road, set 24"x3/4" steel pin, 6" below road surface.  
 From which:  
 A 3"x30" galv iron pipe with brass cap, stamped as shown in diagram, set 2' in ground & raised mound of stone around pipe, bears N 0 13' 41" W 37.8 ft.  
 A lodge pole pine 7" dia. bears S 75 30' E 50.0 ft. scribed C W W E 1/256 S8 BT.  
 A " " " 11" dia bears S 5 40' W 65.9 ft. " " " " "  
 Set steel posts N 27.5 ft. & E 53.0 ft. with bdry. & warning signs attached.  
 Nailed brass washers stamped PLS 848 & bearing tree signs to each tree, painted red band around each tree. (Bearing-True Grid)



Witnesses to above corner.

D. Herburger.  
L. Wyllie

Office of... *SURVEYOR* ..... County of... *Wasilla* .....


State of... *Alaska* ....., I hereby certify that the within instrument was filed in this office for record on the... *26*... day of... *January* ....., 19*81*.

*David H. Kline* by .....  
(COUNTY OFFICIAL) (DEPUTY)

S-63-M

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

① History of original corner establishment:  
Corner not previously established.



② Description of corner evidence found:  
N.A.

③ Description of monument and accessories established to perpetuate the original location of this corner:

Corner falls on edge of 5312 road, set 24"x3/4" steel pin, 6" below road surface.  
 From which:  
 A 3"x30" galv iron pipe with brass cap, stamped as shown in diagram, set 20" in ground & raised mound of stone around pipe, bears N 0 13' 41" W 37.8 ft.  
 A lodge pole pine 7" dia. bears S 75 30' E 50.0 ft. scribed C W W E 1/256 S8 BT.  
 A " " " 11" dia bears S 5 40' W 65.9 ft. " " " " "  
 Set steel posts N 27.5 ft. & E 53.0 ft. with bdry. & warning signs attached.  
 Nailed brass washers stamped PLS 848 & bearing tree signs to each tree, painted red band around each tree. (Bearing-True Grid)



Witnesses to above corner.

D. Herburger.  
L. Wyllie

Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 29 day of January, 1991  
David H. Klein by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)