


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated 1883. Surveyor General record states: Set basalt stone 12x10x8 ins. 8 ins. in ground for 1/4 sec. cor. marked 1/4 on W. face from which:  
 A pine 24 ins. dia. brs. S24°E 57 lks. dist. marked 1/4 S BT  
 A pine 30 ins. dia. brs. N37°W 52 lks. dist. marked 1/4 S BT



Corner remonumented by Robert D. Bagett, OPLS 598, in 1976. His record states:  
 Found basalt stone 12"x10"x8" marked 1/4 on West face firmly set in a mound of stone. From which the original bearing tree:  
 A 24" pine snag bears N57°W 34.3 ft. marked 1/4 S BT.  
 The other BT has been removed in construction on a fence line.  
 At the corner point: Set a 2 1/2"x30" galvanized iron pipe 16" in the ground with brass cap marked as shown (below). From which I scribe new bearing trees:  
 A 10" pine brs. N. 26° E. 43.5 ft. marked T5S R30E 1/4 S36 BT  
 A 10" pine brs. S. 77° W. 42.3 ft. marked T5S R30E 1/4 S35 BT  
 Set a steel fencepost 5' North of corner. Buried original corner stone South and alongside pipe. Surrounded pipe with mound of stone.  
 No record of subsequent monumentation found in Umatilla County survey records.  
 Description of corner evidence found:


Found a 2 1/2" brass cap monument marked as shown in mound of stone.

**ORIGINAL BT**  
 Found a 24 inch diameter Ponderosa Pine N57°W, 34.3 ft. dead and down with scribes visible.

**BAGETT BTS**  
 Found a 12 inch diameter Ponderosa Pine N26°E, 43.5 ft. live and vigorous with blaze evident.

Found a 12 inch diameter Ponderosa Pine S77°W, 42.3 ft. dead and standing with blaze evident.

Distances to existing BTs are to the center of the tree



Description of monument and accessories established to perpetuate the original location of this corner: From the existing found brass cap monument, I take a new Bearing Tree as follows:

**New Bearing Tree:**  
 A 10 inch diameter Ponderosa Pine bears N75°W, 20.43 feet marked 1/4 S35 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on May 8, 1989.

Witnesses: Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distance are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Surveyor County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office for record on the 28<sup>th</sup> day of June 1989  
David H. Kumbain by Kathleen Kumbain  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

Umatilla County Survey  
 Date 6-89  
 Rec'd By KA  
 No. 89-64-2