


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1883 by Frank W. Campbell, under Contract No. 468.

Surveyor General Record States:

40.00 set basalt stone 12x10x8 ins. 8 ins. in ground for 1/4 sec. cor. marked 1/4 on W. face from which:

A pine 24" in diam. brs. S. 24° E. 57 lks. dist. mkd. 1/4 S BT. A pine 30" in diam. brs. N. 37° W. 52 lks. dist. mkd. 1/4 S BT.



No record of subsequent remonumentation found in County Records. Description of corner evidence found:

Found basalt stone 12"x10"x8" marked 1/4 on West face firmly set in a mound of stone. From which the ORIGINAL BEARING TREE:

A 24" pine snag bears N. 57° W. 34.3 ft. marked 1/4 S BT. The other BT has been removed in construction of a fence line.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point: Set a 2 1/2"x30" galvanized iron pipe 16" in the ground with brass cap marked as shown. From which I scribe NEW BEARING TREES:


A 10" pine brs. N. 26° E. 43.5ft. mkd. T5S R30E 1/4 S36 BT. A 10" pine brs. S. 77° W. 42.3ft. mkd. T5S R30E 1/4 S35 BT.

I nailed a brass washer mkd "OPLS 598" to the BT blaze of both trees. Set a steel fence post 5' North of corner. Buried original corner stone South and alongside pipe. Surrounded corner with mound of stone. Used compass with 20° East variation and steel tape, measuring to center of BTs.

REGISTERED PROFESSIONAL LAND SURVEYOR

Robert D. Bagett OREGON JULY 12, 1963 ROBERT D. BAGETT 598

Sept. 30, 1976



Office of... County Surveyor... County of... Umatilla... State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the... day of... 19... (COUNTY OFFICIAL) by (DEPUTY)